

New Flooring Tender – Details

Required Works:

Take up Existing Flooring – Remove all doors as necessary.

Install polysafe flooring including membrane, screed & level as required etc. to below detailed areas

Shave doors and refit

All costs are to include the supply of skips etc. for safe removal of existing floor coverings. All waste products are to be disposed of in a responsible manner and in compliance with current waste regulations.

Please provide full details of product specifications

Area	Room(s)	Base & Current Flooring	Area m2
Humanities	1, 2, 3, 4 & Corridors	Solid base Carpet overlay	1 = 52.8 2 = 52.8 3 = 52.8 4 = 52.8 Corridor = 16.4
Drama	10 & 11	Solid base with wooden floorboard overlay	10 = 62.84 11 = 61.02
Science	7, 8 & Prep Room	Solid base with vinyl tile overlay	7 = 63.51 Prep = 25.75 8 = 63.84
IT	45	Solid base Carpet overlay	46.61
DT / Res Mat	42, Tech Prep Room	Solid base Non-slip flooring	Tech Prep Room = 35.13 42 = 154.52
Business	29, 30, 31, 32	Solid base with vinyl tile overlay	29 = 48.79 30 = 49.46 31 = 50.03 32 = 46.95
Sports	Changing Rooms & Corridors	Solid base with ceramic non-slip tile overlay	Boys = 48.52 + 3.00 Girls = 48.68 + 2.99
Classroom	49	Solid base Wooden Floorboard overlay plus Carpet	41.90

Please return all quotes to tenders@rlt.education, using "Heys - Flooring" as the subject line.

Deadline 12 noon 7th May 2021